



Hydrologic Soil Groups			
Symbol	Name and Description	Rating	Acres
GdC	Gladeville-Rock outcrop complex, 2 to 15 percent slopes; extremely stony	D	0.8
HmC	Hampshire silt loam, 5 to 12 percent slopes	C	7.6
HmD	Hampshire silt loam, 12 to 20 percent slopes	C	4.4
TbC	Talbott silt loam, 2 to 10 percent slopes	C	1.0

NOTE: SOIL INFORMATION ON THIS SHEET WAS OBTAINED FROM NRCS ONLINE SOIL SURVEY DATA. AREAS ARE APPROXIMATE AND ARE FOR REFERENCE ONLY.


[illegible]

- THE PROJECT SITE IS SHOWN ON JURISDICTION, TAX MAP TAX MAP, AS PARCEL PNUM.
- BASE INFORMATION WAS TAKEN FROM A SURVEY PREPARED BY SURVEY COMPANY DATED SURVEY DATE. LITTLEJOHN ENGINEERING ASSOCIATES AND ANY OF THEIR CONSULTANTS SHALL NOT BE HELD RESPONSIBLE FOR THE ACCURACY AND/OR COMPLETENESS OF THAT INFORMATION SHOWN HEREON OR ANY ERRORS OR OMISSIONS RESULTING FROM SUCH.
- THE SITE LAYOUT IS BASED ON REFERENCE POINTS AS NOTED.
- THE CONTRACTOR SHALL CHECK ALL EXISTING CONDITIONS, (i.e. INVERTS, UTILITY ROUTINGS, UTILITY CROSSINGS, AND DIMENSIONS) IN THE FIELD PRIOR TO COMMENCEMENT OF WORK. REPORT ANY DISCREPANCIES TO THE ENGINEER.
- THE CONTRACTOR SHALL VERIFY THE EXACT LOCATION OF ALL EXISTING UTILITIES. TAKE CARE TO PROTECT UTILITIES THAT ARE TO REMAIN. REPAIR ANY DAMAGE ACCORDING TO LOCAL STANDARDS AND AT THE CONTRACTOR'S EXPENSE. COORDINATE ALL CONSTRUCTION WITH THE APPROPRIATE UTILITY COMPANY. THE CONTRACTOR SHALL CALL NATIONAL ONE CALL (811) 72 HOURS PRIOR TO PROCEEDING WITH ANY EXCAVATION.
- THE CONTRACTOR SHALL CONFORM TO ALL LOCAL CODES AND RECEIVE APPROVAL WHERE NECESSARY BEFORE CONSTRUCTION.
- EXISTING PAVEMENT OF PUBLIC ROADWAYS SHALL BE PATCHED IN ACCORDANCE WITH LOCAL AGENCY STANDARDS WHEREVER UTILITY INSTALLATION REQUIRES REMOVAL OF THE EXISTING PAVEMENT. COORDINATE PAVEMENT TRENCHING LOCATIONS WITH CITY CIVIL, PLUMBING AND ELECTRICAL PLANS.
- PROVIDE A SMOOTH TRANSITION BETWEEN EXISTING PAVEMENT AND NEW PAVEMENT. SLIGHT FIELD ADJUSTMENT OF FINAL GRADES MAY BE NECESSARY.
- DIMENSIONS ARE TO FACE OF CURB AND/OR EXTERIOR FACE OF BUILDING UNLESS OTHERWISE NOTED.
- CONCRETE FOR CURBS AND SIDEWALKS SHALL BE 3500 PSI CONCRETE.
- ANY WORK UNACCEPTABLE TO THE OWNER'S REPRESENTATIVE OR TO THE LOCAL GOVERNING AUTHORITY SHALL BE REPAIRED OR REPLACED BY THE CONTRACTOR AT NO ADDITIONAL EXPENSE TO THE OWNER.
- ACCESSIBLE RAMPS SHALL HAVE A MAXIMUM SLOPE OF 1:12. GRADES WITHIN ACCESSIBLE SPACES SHALL BE MAXIMUM 2% IN ALL DIRECTIONS.
- THE PROPOSED BUILDING SHALL BE LAID OUT UTILIZING THE EXISTING STRUCTURE AS A CONTROL POINT AND THE ARCHITECTURAL DRAWINGS. DIMENSIONS SHOWN TO THE PROPOSED BUILDING ARE CALCULATED TO THE FACE OF EXTERIOR WALL. SEE ARCHITECTURAL PLANS FOR EXACT BUILDING DIMENSIONS.
- CURBS SHALL BE PARALLEL TO THE CENTERLINE OF DRIVES. THE CURB SHALL BE PLACED ONLY AFTER HAVING ALL BREAK POINTS (PC & PT OF CURVES) LOCATED AT THE FACE OF CURB OR AT A CONSISTENT OFFSET BY A REGISTERED LAND SURVEYOR.
- THE CONTRACTOR SHALL COMPLY WITH ALL PERTINENT PROVISIONS OF THE MANUAL OF ACCIDENT PREVENTION AND CONSTRUCTION ISSUED BY AGC OF AMERICA, INC. AND THE SAFETY AND HEALTH REGULATIONS OF CONSTRUCTION ISSUED BY THE U.S. DEPARTMENT OF LABOR.
- THE CONTRACTOR SHALL PAVE IN THE DIRECTION OF TRAFFIC.
- THE CONTRACTOR SHALL COLD PLANE IN THE DIRECTION OF TRAFFIC.
- THE CONTRACTOR WILL BE REQUIRED TO ADJUST GRADES OF INTERSECTING STREETS, ALLEYS, PUBLIC ENTRANCES AND PRIVATE DRIVES AS DIRECTED BY THE ENGINEER.
- ALL ROADWAY AND SIDEWALK CONSTRUCTION SHALL CONFORM TO THE REQUIREMENTS AND SPECIFICATIONS OF LOCAL GOVERNING AGENCY.
- ALL CONSTRUCTION MATERIALS AND INSTALLATION SHALL CONFORM TO LOCAL GOVERNING AGENCY AND STATE DOT REGULATIONS AND SPECIFICATIONS.
- ALL CURBING WILL BE REQUIRED TO ADJUST TO THE GRADES OF INTERSECTING STREETS, ALLEYS, PUBLIC ENTRANCES, AND PRIVATE DRIVES AS DIRECTED BY THE ENGINEER.

3. ALL MATERIALS BEING REMOVED AND NOT RELOCATED UNDER THE NEW CONSTRUCTION, INCLUDING TREES AND SHRUBS, SIGNS, UTILITY STRUCTURES, ETC., SHALL BE FIRST OFFERED TO THE OWNER'S REPRESENTATIVE AND IF NOT ACCEPTED SHALL THEN BE PROPERLY DISPOSED OF BY THE CONTRACTOR.
2. THE CONTRACTOR IS RESPONSIBLE FOR LOCATING ALL CHARTED AND UNCHARTED UTILITIES. TAKE CARE TO PROTECT UTILITIES THAT ARE TO REMAIN. REPAIR ANY DAMAGE ACCORDING TO LOCAL STANDARDS AND AT THE CONTRACTOR'S EXPENSE. COORDINATE ALL CONSTRUCTION WITH THE APPROPRIATE UTILITY COMPANY.
3. THE CONTRACTOR SHALL VERIFY THE LIMITS OF DEMOLITION WITH THE OWNER'S REPRESENTATIVE PRIOR TO COMMENCEMENT OF WORK.
4. IN AREAS WHERE EXISTING PAVEMENT, WALKS, OR CURBS ARE TO BE REMOVED, SAW CUT TO PROVIDE A CLEAN EDGE. COORDINATE EXTENT OF PAVEMENT DEMOLITION WITH THE LIMIT OF NEW IMPROVEMENTS ON THE SITE LAYOUT PLAN & UTILITY INSTALLATION.
5. CONTRACTOR SHALL COORDINATE PHASING OF THE DEMOLITION WITH THE OWNER'S REPRESENTATIVE AND LOCAL GOVERNING AGENCY PRIOR TO BEGINNING WORK. DISRUPTION OF EXISTING UTILITY SERVICES AND TRAFFIC PATTERNS SHALL BE MINIMIZED TO THE EXTENT POSSIBLE AND INITIATED ONLY AFTER APPROVAL BY THE LOCAL GOVERNING AGENCY AND THE UTILITY COMPANIES.
6. CAVITIES LEFT BY STRUCTURE REMOVAL SHALL BE SUITABLY BACKFILLED AND COMPACTED IN ACCORDANCE WITH THESE PLANS AND SPECIFICATIONS.
7. THE CONTRACTOR SHALL USE WATER SPRINKLING AND OTHER SUITABLE METHODS AS NECESSARY TO CONTROL DUST AND DIRT CAUSED BY THE DEMOLITION WORK.
8. THE CONTRACTOR IS RESPONSIBLE FOR ALL DEMOLITION AND REMOVAL NECESSARY TO ACCOMPLISH THE PROPOSED IMPROVEMENTS SHOWN ON THESE PLANS.
9. THE CONTRACTOR SHALL PRESERVE AND PROTECT SURVEY CONTROL POINTS AND SHALL BE RESPONSIBLE FOR REPLACEMENT OF ANY DISTURBED CONTROL POINTS.
10. EXISTING LIGHT STANDARDS BEING REMOVED SHALL BE FIRST OFFERED TO THE OWNER PRIOR TO DISPOSING OF THEM. COORDINATE LIGHTING DEMOLITION AND LAYOUT WITH THE ELECTRICAL DRAWINGS.
11. RELOCATION OF EXISTING PLANT MATERIALS SHALL BE COORDINATED WITH THE OWNER AND RELOCATED TO A DESIGNATED AREA ON SITE.
12. EXISTING TREES TO BE PRESERVED ARE TO BE BARRICADED BEFORE BEGINNING CONSTRUCTION IN ACCORDANCE WITH THE TREE PRESERVATION NOTES AND DETAIL ON THE LANDSCAPE PLAN.
13. NO UTILITY OR STORM SEWER LINES SHALL BE DEMOLISHED UNTIL THE NEW LINES HAVE BEEN INSTALLED AND ARE PLACED INTO OPERATION.
14. THE CONTRACTOR SHALL INCORPORATE INTO HIS WORK ANY ISOLATION VALVES OR TEMPORARY PLUGS REQUIRED TO CONSTRUCT NEW UTILITY LINES AND DEMOLISH EXISTING UTILITY LINES.
15. SELECTIVE CLEARING CONSISTING OF REMOVAL OF VINES, SAPLINGS UNDER 1" DIAMETER AND UNDERBRUSH SHALL BE PERFORMED IN TREE PRESERVATION AREAS INTERNAL TO THE PROJECT AND NOTED ON PLANS.
16. WHERE WATER LINE AND SEWER LINE ABANDONMENT IS PLANNED, THE CONTRACTOR MAY ABANDON WATER LINES AND SEWER LINES IN PLACE WHERE THEY OCCUR AT LEAST 24" (TO TOP OF PIPE) BELOW FINAL SUBGRADE ELEVATIONS AND OUTSIDE THE BUILDING FOOT PRINT. ALL UTILITY LINES BEING ABANDONED IN PLACE SHALL HAVE ALL ENDS PERMANENTLY CLOSED USING A CONCRETE PLUG.
17. WHERE EXISTING IRRIGATION LINED LIE WITHIN THE AREA AFFECTED BY THE PROPOSED CONSTRUCTION, THE CONTRACTOR SHALL REWORK THE EXISTING IRRIGATION SYSTEMS IN ACCORDANCE WITH DIRECTIVES NOTED ON THE LANDSCAPE PLAN. SERVICE SHALL BE MAINTAINED DURING CONSTRUCTION TO THE LANDSCAPED AREAS CURRENTLY IRRIGATED.

1. THE DISTURBED AREA FOR THIS PROJECT IS APPROXIMATELY DISBURTED AREA ACRES.
2. THE SUBJECT PROPERTY DOES LIE/DOES NOT LIE WITHIN A SPECIAL FLOOD HAZARD ZONE ACCORDING TO COMMUNITY PANEL NO. FEMA PANEL # OF THE F.E.M.A. FLOOD INSURANCE RATE MAPS FOR PROJECT COUNTY COUNTY, PROJECT STATE, WITH AN EFFECTIVE DATE OF FEMA PANEL DATE.
3. CONSTRUCT SILT BARRIERS BEFORE BEGINNING GRADING OPERATIONS.
4. MULCH AND SEED ALL DISTURBED AREAS AS SOON AS POSSIBLE AFTER FINAL GRADING IS COMPLETED, UNLESS OTHERWISE INDICATED. CONTRACTOR SHALL TAKE WHATEVER MEANS NECESSARY TO ESTABLISH PERMANENT SOIL STABILIZATION.
5. THE CONTRACTOR SHALL VERIFY THE EXACT LOCATION OF ALL EXISTING UTILITIES. TAKE CARE TO PROTECT UTILITIES THAT ARE TO REMAIN. REPAIR ANY DAMAGE ACCORDING TO LOCAL STANDARDS AND AT THE CONTRACTOR'S EXPENSE. COORDINATE ALL CONSTRUCTION WITH THE APPROPRIATE UTILITY COMPANY.
6. PROVIDE TEMPORARY CONSTRUCTION ACCESS(ES) AT THE POINT(S) WHERE CONSTRUCTION VEHICLES EXIT THE CONSTRUCTION AREA. MAINTAIN PUBLIC ROADWAYS FREE OF TRACKED MUD AND DIRT.
7. THE CONTRACTOR SHALL COORDINATE THE EXACT LOCATION OF THE STORM DRAIN CONNECTIONS AT THE BUILDING WITH THE PLUMBING PLANS.
8. THE CONTRACTOR SHALL CHECK ALL EXISTING GRADES AND DIMENSIONS IN THE FIELD PRIOR TO BEGINNING WORK AND REPORT ANY DISCREPANCIES TO THE ENGINEER.
9. THE CONTRACTOR SHALL ADJUST THE CASTINGS OF ALL NEW AND EXISTING STRUCTURES TO MATCH PROPOSED FINISH GRADES.
10. THE CONTRACTOR SHALL COMPLY WITH ALL PERTINENT PROVISIONS OF THE MANUAL OF ACCIDENT PREVENTION AND CONSTRUCTION ISSUED BY AGC OF AMERICA, INC. AND THE SAFETY AND HEALTH REGULATIONS OF CONSTRUCTION ISSUED BY THE U.S. DEPARTMENT OF LABOR.
11. PROPOSED CONTOUR LINES AND SPOT ELEVATIONS ARE THE RESULT OF AN ENGINEERED GRADING DESIGN AND REFLECT A PLANNED INTENT WITH REGARD TO DRAINAGE AND MOVEMENT OF MATERIALS. SHOULD THE CONTRACTOR HAVE ANY QUESTION OF THE INTENT OR ANY PROBLEM WITH THE CONTINUITY OF GRADES, THE ENGINEER SHALL BE CONTACTED IMMEDIATELY.
12. ALL CUT AND FILL SLOPES SHALL BE 3:1 HORIZONTAL TO 1 VERTICAL OR FLATTER UNLESS OTHERWISE INDICATED ON THE PLANS.
13. ALL PIPES UNDER EXISTING PAVED AREAS SHALL BE BACKFILLED TO THE TOP OF SUBGRADE WITH CRUSHED STONE.
14. MINIMUM GRADE ON ASPHALT OR CONCRETE PAVING SHALL BE 1.0%. THE MAXIMUM GRADES WITHIN ACCESSIBLE SPACES SHALL BE 2% IN ANY DIRECTION.
15. CONTRACTOR SHALL CONFORM TO ALL APPLICABLE CODES AND OBTAIN APPROVAL AS NECESSARY BEFORE BEGINNING CONSTRUCTION.
16. ALL EARTHWORK, INCLUDING THE EXCAVATED SUBGRADE AND EACH LAYER OF FILL, SHALL BE MONITORED AND APPROVED BY A QUALIFIED GEOTECHNICAL ENGINEER, OR HIS REPRESENTATIVE.
17. IF ANY SPRINGS OR UNDERGROUND STREAMS ARE EXPOSED DURING CONSTRUCTION PERMANENT FRENCH DRAINS MAY BE REQUIRED. THE DRAINS SHALL BE SPECIFIED AND LOCATED DURING CONSTRUCTION AS REQUIRED BY THE CONDITIONS WHICH ARE ENCOUNTERED, AND SHALL BE APPROVED BY THE ENGINEER.
18. THIS GRADING & DRAINAGE PLAN IS NOT A DETERMINATION OR GUARANTEE OF THE SUITABILITY OF THE SUBSURFACE CONDITIONS FOR THE WORK INDICATED. A GEOTECHNICAL SOILS REPORT HAS BEEN PREPARED AND IS AVAILABLE FROM THE OWNER. DETERMINATION OF THE SUBSURFACE CONDITIONS FOR THE WORK INDICATED IS SOLELY THE RESPONSIBILITY OF THE CONTRACTOR.
19. THE CONTRACTOR SHALL TAKE SPECIAL CARE TO COMPACT FILL SUFFICIENTLY AROUND AND OVER ALL PIPES, STRUCTURES, VALVE STEMS, ETC., INSIDE THE PROPOSED PAVED AREAS TO AVOID SETTLEMENT. ANY SETTLEMENT DURING THE WARRANTY PERIOD SHALL BE RESTORED BY THE CONTRACTOR AT NO ADDITIONAL COST TO THE OWNER.
20. IN NO CASE SHALL SLOPE, HEIGHT, SLOPE INCLINATION, OR EXCAVATION DEPTH, INCLUDING TRENCH CONSTRUCTION, EXCEED THOSE SPECIFIED IN LOCAL, STATE AND FEDERAL REGULATIONS, SPECIFICALLY THE CURRENT OSHA HEALTH AND SAFETY STANDARDS FOR EXCAVATIONS (29 CFR PART 1926) SHALL BE FOLLOWED.
21. DO NOT DISTURB VEGETATION OR REMOVE TREES EXCEPT WHEN NECESSARY FOR GRADING PURPOSES.
22. STRIP TOPSOIL FROM ALL CUT AND FILL AREAS AND STOCKPILE UPON COMPLETION OF GENERAL GRADING OVER ALL DISTURBED AREAS, TO A MINIMUM DEPTH OF 6". CONTRACTOR SHALL SUPPLY ADDITIONAL TOP SOIL IF INSUFFICIENT QUANTITIES EXIST ON SITE.
23. TOP OF GRATE ELEVATIONS AND LOCATION OF COORDINATES FOR DRAINAGE STRUCTURES SHALL BE AS SHOWN ON THE DETAIL, UNLESS NOTED OTHERWISE. THE GRATES SHALL SLOPE LONGITUDINALLY WITH THE PAVEMENT GRADES.
24. ALL DRAINAGE CONSTRUCTION MATERIALS AND INSTALLATION SHALL CONFORM TO THE REQUIREMENTS AND SPECIFICATIONS OF THE LOCAL GOVERNING AGENCY.
25. POSITIVE DRAINAGE SHALL BE ESTABLISHED AS THE FIRST ORDER OF WORK AND SHALL BE MAINTAINED AT ALL TIMES DURING AND AFTER CONSTRUCTION. SOIL SOFTENED BY PERCHED WATER IN FOUNDATION AND PAVEMENT AREAS MUST BE UNDERCUT AND REPLACED WITH SUITABLE FILL MATERIALS APPROVED BY THE GEOTECHNICAL ENGINEER. GROUNDWATER INFILTRATION INTO EXCAVATIONS SHOULD BE EXPECTED, AND THE WATER SHALL BE REMOVED USING GRAVITY DRAINAGE OR PUMPING.
26. REINFORCED CONCRETE STORM DRAINAGE PIPE SHALL BE CLASS III, WALL "B". HDPE SHALL BE CORRUGATED, SMOOTH WALL N-12 PIPE WITH SOIL TIGHT JOINTS.
27. FILL SLOPES 3:1 AND GREATER SHALL BE PLACED AND COMPACTED 5' BEYOND PROPOSED LIMITS AND THEN EXCAVATED BACK TO THE PROPOSED LOCATION.
28. THE CONTRACTOR SHALL PROVIDE AN ASBUILT SURVEY STAMPED BY A LICENSED SURVEYOR IN THE STATE OF PROJECT STATE OF ALL PUBLIC STORM SYSTEMS, ONSITE DETENTION PONDS, AND WATER QUALITY MEASURES VERIFYING COMPLIANCE WITH DESIGN DOCUMENTS.
29. THE CONTRACTOR SHALL NOTIFY THE ENGINEER 72 HOURS PRIOR TO INSTALLATION OF THE WATER QUALITY DEVICES.
30. ALL FILL MATERIAL SHALL BE APPROVED BY THE GEOTECHNICAL ENGINEER PRIOR TO PLACEMENT. THIS MATERIAL SHALL BE PLACED IN LIFTS DIRECTED BY THE GEOTECHNICAL ENGINEER AND COMPACTED AS SPECIFIED BY THE GEOTECHNICAL ENGINEER TO XX% STANDARD/MODIFIED PROCTOR.
31. THE LOCATION OF ALL DIVERSION SWALES AND DITCHES SHALL BE FIELD ADJUSTED TO AVOID TREES AS POSSIBLE. THE CONTRACTOR SHALL WALK THE ALIGNMENT OF THESE SWALES AND DITCHES IN THE FIELD TO VERIFY AVOIDANCE OF TREES.
32. SEDIMENT REMOVED FROM SEDIMENT CONTROL STRUCTURES IS TO BE PLACED AT A SITE APPROVED BY THE ENGINEER. IT SHALL BE TREATED IN A MANNER SO THAT THE AREA AROUND THE DISPOSAL SITE WILL NOT BE CONTAMINATED OR DAMAGED BY THE SEDIMENT IN THE RUN-OFF. COST FOR THIS TREATMENT IS TO BE INCLUDED IN PRICE BID FOR EARTHWORK. THE CONTRACTOR SHALL OBTAIN THE DISPOSAL SITE AS PART OF THIS WORK.
33. STOCKPILED TOPSOIL OR FILL MATERIAL IS TO BE TREATED SO THE SEDIMENT RUN-OFF WILL NOT CONTAMINATE SURROUNDING AREAS OR ENTER NEARBY STREAMS.
34. ANY SITE USED FOR DISPOSAL AND/OR STOCKPILE OF ANY MATERIAL SHALL BE PROPERLY PERMITTED FOR SUCH ACTIVITY. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO SEE THAT ALL REQUIRED PERMITS ARE SECURED FOR EACH PROPERTY UTILIZED. A COPY OF THE APPROVED PERMIT MUST BE PROVIDED TO THE INSPECTOR PRIOR TO COMMENCEMENT OF WORK ON ANY PROPERTY. FAILURE TO DO SO MAY RESULT IN THE CONTRACTOR REMOVING ANY ILLEGALLY PLACED MATERIAL AT HIS OWN EXPENSE.
35. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO WASTE EXCESS EARTH MATERIAL OFF SITE AT NO ADDITIONAL COST TO THE OWNER. THE CONTRACTOR SHALL FIRST OFFER THE EXCESS MATERIAL TO THE OWNER. IF NOT ACCEPTED BY THE OWNER, THE CONTRACTOR SHALL DISPOSE OF EARTH MATERIAL OFF SITE. IT SHALL ALSO BE THE CONTRACTOR'S RESPONSIBILITY TO IMPORT SUITABLE MATERIAL (AT NO ADDITIONAL COST TO THE OWNER) FOR EARTHWORK OPERATIONS IF SUFFICIENT AMOUNTS OF EARTH MATERIAL ARE NOT AVAILABLE ON SITE.
36. SEGMENTAL WALLS SHALL BE PROVIDED BY THE CONTRACTOR AS A DESIGN BUILD. WALL DESIGN PLANS STAMPED BY A REGISTERED ENGINEER IN THE STATE OF THE PROJECT SHALL BE SUBMITTED TO THE ENGINEER AS A SHOP DRAWING. THE CONTRACTOR IS RESPONSIBLE FOR OBTAINING ANY GEOTECHNICAL INFORMATION NECESSARY TO PROPERLY DESIGN THE WALL.

1. THE PROJECT SITE IS SHOWN ON JURISDICTION, TAX MAP TAX MAP, AS PARCEL PARCEL NUM.
2. THE SANITARY SEWER SHALL BE OF THE MATERIAL INDICATED ON THE PLAN. POLYVINYLCHLORIDE (PVC) SHALL BE (SDR35). DUCTILE IRON PIPE (D.I.P.) SHALL BE CLASS 52.
3. ALL WATER LINES, SEWER LINES, AND APPURTENANCES SHALL BE OF MATERIALS AND CONSTRUCTION THAT CONFORM TO THE LOCAL AGENCY STANDARDS AND SPECIFICATIONS.
4. PROVIDE A MINIMUM ____" OF COVER OVER ALL WATER LINES.
5. THE CONTRACTOR SHALL MAINTAIN 10 FEET HORIZONTAL SEPARATION BETWEEN SANITARY SEWER LINES AND WATER LINES. WHERE THESE CRITERIA CANNOT BE MET, THE CONTRACTOR SHALL MAINTAIN 18" VERTICAL SEPARATION BETWEEN WATER AND SEWER LINES.
6. THE CONTRACTOR SHALL FIELD VERIFY THE EXACT HORIZONTAL AND VERTICAL LOCATION OF EXISTING MANHOLES OR SANITARY SEWER LINES AT THE POINT OF CONNECTION PRIOR TO THE COMMENCEMENT OF ORDERING OF MATERIALS, CONSTRUCTION OR REPORT ANY DISCREPANCIES TO THE ENGINEER IMMEDIATELY.
7. THE CONTRACTOR SHALL BE RESPONSIBLE FOR COORDINATING THE SEQUENCING OF CONSTRUCTION FOR ALL UTILITY LINES SO THAT WATER LINES DO NOT CONFLICT WITH SANITARY SEWERS, SANITARY SEWER SERVICES, STORM SEWERS, OR ANY OTHER UTILITY OR STRUCTURE, EXISTING OR PROPOSED.
8. THE LOCATION OF EXISTING UTILITIES SHOWN ON THESE PLANS ARE APPROXIMATE ONLY. THE CONTRACTOR SHALL NOTIFY EACH INDIVIDUAL UTILITY OWNER OF HIS PLAN OF OPERATION IN THE AREA OF THE UTILITIES. PRIOR TO COMMENCING WORK, THE CONTRACTOR SHALL CONTACT THE UTILITY OWNERS AND REQUEST THEM TO PROPERLY LOCATE THEIR RESPECTIVE UTILITY ON THE GROUND. THIS NOTIFICATION SHALL BE GIVEN AT LEAST THREE (3) BUSINESS DAYS PRIOR TO COMMENCEMENT OF OPERATIONS AROUND THE UTILITY.
9. BEFORE CONNECTIONS ARE MADE INTO EXISTING UTILITIES, THE NEW LINES ARE TO BE FLUSHED AND TESTED BY THE CONTRACTOR IN ACCORDANCE WITH THE LOCAL WATER AND SEWER DEPARTMENT SPECIFICATIONS.
10. ALL TRENCHES CUT IN EXISTING ROADS OR DRIVES SHALL UTILIZE A CLEAN SAW CUT AND SHALL BE BACKFILL (100%) TO FINAL SUBGRADE WITH #57 STONE. REPAIR ROADS PER LOCAL AGENCY REQUIREMENTS.
11. REPAIR ALL DAMAGE TO EXISTING FEATURES (i.e. DRIVES, ROADS, YARDS, LANDSCAPING, ETC.,...) TO PRE-CONSTRUCTION CONDITION.
12. THE CONTRACTOR SHALL PROVIDE ALL HORIZONTAL AND VERTICAL BENDS TO ATTAIN THE ALIGNMENT INDICATED ON THE PLANS. PROVIDE VERTICAL BENDS WHERE NECESSARY TO ALLOW WATER LINES TO PASS UNDER OR OVER OTHER UTILITY LINES. (ALL BENDS AND BRACES NEEDED MAY NOT BE ACTUALLY SHOWN). PROVIDE BRACING AND/OR RODDING AT ALL BENDS AND TEES AS REQUIRED BY WATER DEPARTMENT.
13. REDUCED PRESSURE BACKFLOW PREVENTER (RPBP) OR DUAL CHECK WILL BE REQUIRED ON ALL TESTS AND FILL LINES (JUMPER) NEEDED FOR WATER MAIN CONSTRUCTION AND MUST BE APPROVED BY THE WATER DEPARTMENT.
14. COORDINATE THE EXACT LOCATION OF ALL UTILITIES ENTERING THE BUILDING WITH THE PLUMBING PLANS.
15. WATER METERS SHALL BE AT LEAST 22" BUT NO MORE THAN 26" FROM TOP OF METER TO PROPOSED FINISHED GRADE.
16. THE CONTRACTOR SHALL VERIFY REQUIRED PIPE LENGTHS. EXISTING PIPE MATERIAL AND SIZES AS SHOWN ON PLANS.
17. REPAIR EXISTING PAVEMENT, CURBS, WALKS, LANDSCAPING, ETC. THAT ARE DAMAGED BY CONSTRUCTION ACTIVITIES TO A LIKE NEW CONDITION AT NO ADDITIONAL COST TO THE OWNER.
18. THE PROPOSED GAS LINE CONSTRUCTION AND INSTALLATION SHALL BE COORDINATED WITH THE LOCAL GAS COMPANY BY THE CONTRACTOR.
19. THE PROPOSED ELECTRIC LINE CONSTRUCTION AND INSTALLATION SHALL BE COORDINATED WITH THE LOCAL ELECTRIC COMPANY BY THE CONTRACTOR.
20. THE PROPOSED TELEPHONE LINE CONSTRUCTION AND INSTALLATION SHALL BE COORDINATED WITH THE LOCAL TELEPHONE COMPANY BY THE CONTRACTOR.
21. WHERE DRAINAGE OR UTILITY LINES OCCUR IN PROPOSED FILL AREAS, THE FILL MATERIAL IS TO BE PLACED AND COMPACTED TO XX% STANDARD/MODIFIED PROCTOR OF MAXIMUM DRY DENSITY ACCORDING TO ASTM D698/D1557 PRIOR TO INSTALLATION OF DRAINAGE OR UTILITY LINES. FILL IS TO BE INSPECTED BY A PROFESSIONAL GEOTECHNICAL ENGINEER TESTING FIRM EMPLOYED BY THE OWNER. RESULTS OF THE TEST SHALL BE FURNISHED TO THE OWNER'S REPRESENTATIVE. CONTRACTOR TO PAY FOR ANY RETESTING.
22. THE CONTRACTOR SHALL ADJUST THE ALIGNMENT OF THE WATER LINES (HORIZONTALLY AND/OR VERTICALLY) TO ALLOW THE REQUIRED BRACING AT BENDS AND TEES.
23. EXISTING CASTINGS LOCATED IN FILL/CUT AREAS SHALL BE ADJUSTED TO ENSURE THAT THE TOP OF CASTING IS FLUSH WITH THE FINISHED GRADE.
24. WATER SERVICES SHALL BE ¾" TYPE K COPPER AND SHALL INCLUDE CORPORATION STOPS, CURB STOPS, PRESENT METER BOX AND ALL OTHER FITTINGS AS REQUIRED BY LOCAL DEPARTMENT.
25. THE OUTSIDE OF ALL MANHOLES SHALL BE COATED WITH BITUMINOUS PAINT.
26. ALL WATER LINE SERVICES SHALL TERMINATE AT A METER BOX LOCATED 10 FEET FROM THE R.O.W. LINE.
27. THE CONTRACTOR WILL PROVIDE ALL NECESSARY PROTECTIVE MEASURES TO SAFEGUARD EXISTING UTILITIES FROM DAMAGE DURING CONSTRUCTION OF THIS PROJECT. IN THE EVENT THAT SPECIAL EQUIPMENT IS REQUIRED TO WORK OVER AND AROUND THE UTILITIES, THE CONTRACTOR WILL BE REQUIRED TO FURNISH SUCH EQUIPMENT AT NO ADDITIONAL COST TO THE OWNER.
28. PRIOR TO SUBMITTING HIS BID, THE CONTRACTOR WILL BE SOLELY RESPONSIBLE FOR CONTACTING OWNERS OF ALL AFFECTED UTILITIES IN ORDER TO DETERMINE THE EXTENT TO WHICH UTILITY RELOCATIONS AND/OR ADJUSTMENTS WILL HAVE UPON THE SCHEDULE OF WORK FOR THE PROJECT. WHILE SOME WORK MAY BE REQUIRED AROUND UTILITY FACILITIES THAT WILL REMAIN IN PLACE, OTHER UTILITY FACILITIES MAY NEED TO BE ADJUSTED CONCURRENTLY WITH THE CONTRACTOR'S OPERATIONS.
29. ALL CONNECTIONS TO EXISTING MANHOLES SHALL BE BY THE CORING AND RESILIENT SEAL METHOD.
30. FIRE HYDRANT ASSEMBLIES INCLUDE THE APPROPRIATE SIZED TEE (WITH KICKER), 6" LINE TO HYDRANT, 6" GATE VALVE (WITH VALVE BOX), AND FIRE HYDRANT (WITH KICKER). HYDRANTS SHALL BE INSTALLED AT LOCATIONS SHOWN ON THE PLANS.
31. THE CONCRETE CAPS AND ENCASEMENTS ON WATER AND SEWER LINES SHALL BE A MINIMUM OF 6" THICK. USE 3000 PSI CONCRETE.
32. ALL SANITARY SEWER SERVICES SHALL BE 6" DIAMETER AND EXTEND 10 FEET BEYOND THE PROPERTY LINE.
33. CONTRACTOR SHALL MARK THE LOCATION OF ALL NEW PVC LINES WITH #8 WIRE.
34. BACKFLOW PREVENTION DEVICE FOR THE DOMESTIC WATER SERVICE SHALL BE LOCATED INSIDE THE BUILDING, SEE PLUMBING PLANS.
35. SIAMESE STAND PIPE TO BE GALVANIZED STEEL.
36. ALL PROPOSED LOT CORNERS SHALL BE FIELD STAKED PRIOR TO CONSTRUCTION OF SANITARY SEWERS. CONTROL POINTS ARE AS SHOWN ON THE SITE LAYOUT PLAN.
37. THE HOME BUILDER SHALL VERIFY THE SANITARY SEWER SERVICE ELEVATION PRIOR TO SETTING THE FINISHED FLOOR ELEVATIONS FOR ALL LOTS. THE SANITARY SEWER MAIN AND SERVICES WERE DESIGNED BASED ON SETTING MINIMUM FINISHED FLOOR ELEVATIONS ON A NUMBER OF CRITICAL LOTS. THE HOME BUILDER SHALL ADHERE TO THE MINIMUM FINISHED FLOOR ELEVATIONS LISTED ON THE SANITARY SEWER SHEETS.
38. SEWER SERVICES TO BE 6" DIAMETER PVC AT A MINIMUM SLOPE OF 1.0% UNLESS SHOWN OTHERWISE ON THE DRAWINGS. LINES SHALL START 5' BEYOND THE BUILDINGS. COORDINATE CONNECTION POINTS WITH THE BUILDING PLUMBING DRAWINGS. PROVIDE A MINIMUM 30" OF COVER OVER ALL SEWER SERVICES IN GRASS AREAS AND 48" OF COVER IN PAVED AREAS.
39. ALL FIRE LINES SHALL BE INSTALLED BY A SPRINKLER CONTRACTOR LICENSED IN THE STATE OF THE PROJECT.



1935 21st Avenue South, Nashville, Tennessee 37212
T 615.385.4144 F 615.385.4020 www.lea-inc.com

314-261-7352

FINAL P.U.D.
LKQ OFFICE AT
THE CROSSINGS
5846 CROSSINGS BLVD
NASHVILLE, TENNESSEE 37013
Case No. 84-87P-004

[illegible]

PROJECT NUMBER
514717001

DRAWING NUMBER

DRAWING NAME

SITE NOTES

METRO NOTES:

"AS THE DESIGN ENGINEER RESPONSIBLE FOR THE DEVELOPMENT OF THESE PLANS, I HEREBY CERTIFY THAT THIS PROJECT, WHICH SHALL DISTURB ONE (1) OR MORE ACRES, HAS BEEN GRANTED COVERAGE UNDER THE TENNESSEE GENERAL STORM WATER PERMIT ADDRESSING CONSTRUCTION SITE RUNOFF ACTIVITIES BY THE TENNESSEE DIVISION OF WATER POLLUTION CONTROL." (TNR# 241498)

Michael Towles
TN REGISTERED ENGINEER

04/17/2017
DATE

I, MICHAEL GREGORY TOWLES, A REGISTERED EROSION CONTROL SPECIALIST HAVE REVIEWED THE PLAN FOR SUFFICIENT ONSITE TEMPORARY EROSION AND SEDIMENT CONTROL PROVISIONS.

Michael Towles
EROSION CONTROL SPECIALIST

04/17/2017
DATE

SITE BM #1:
TAG BOLT #8229V7 ON FIRE HYDRANT
LOCATED IN SOUTH ROW OF CROSSINGS BLVD
±750' WEST OF THE INTERSECTION OF
CROSSINGS BLVD AND OLD FRANKLIN RD
ELEV: 601.22


SITE BM #2:
BOLT BELOW ARROW ON FIRE HYDRANT
LOCATED IN SOUTH ROW OF CROSSINGS BLVD
±255' WEST OF THE INTERSECTION OF
CROSSINGS BLVD AND OLD FRANKLIN RD
ELEV: 612.01

PROJECT BM:
NAVD 88 (GPS DERIVED)

EROSION CONTROL KEYNOTES		
CODE	DESCRIPTION	DET #/SHT #
EC1	TEMPORARY CONSTRUCTION ENTRANCE	
EC2	SILT FENCE OR WEIGHTED SEDIMENT TUBES	
EC3	INLET PROTECTION	
EC4	TREE PROTECTION	
EC5	DIVERSION DITCH	
EC6	ROCK CHECK DAM	
EC7	RIPRAP AT HEADWALL	
EC8a	SEDIMENT TRAP OUTLET STRUCTURE	
EC8b	TEMPORARY SEDIMENT TRAP	
EC9	TEMPORARY SEEDING OR MULCHING	
EC10	POROUS BAFFLE	
EC11	BIODEGRADABLE EROSION CONTROL BLANKETS WITH HYDRO SEEDING	
EC12	PERMANENT EROSION CONTROL BLANKETS WITH HYDRO SEEDING	

LEGEND

- L O D — LIMIT OF DISTURBANCE
— T P — TREE PROTECTION
— S F — SILT FENCE



Littlejohn

A Division of S&ME

1935 21st Avenue South, Nashville, Tennessee 37212

T 615.385.4144 F 615.385.4020 www.littlejohn.com

KP Nashville, LLC

8025 Forsyth Blvd.

St. Louis, Missouri

314-261-7352

FINAL P.U.D.

LKQ OFFICE AT

THE CROSSINGS

5846 Crossings Blvd

Nashville, Tennessee 37013

Case No. 84-87P-004

NO.	DATE	DESCRIPTION	BY	CHK	APV

PROJECT NUMBER

514717001

DRAWING NUMBER

C2.0

DRAWING NAME

INITIAL SEDIMENT & EROSION CONTROL PLAN

METRO NOTES:

"AS THE DESIGN ENGINEER RESPONSIBLE FOR THE DEVELOPMENT OF THESE PLANS, I HEREBY CERTIFY THAT THIS PROJECT, WHICH SHALL DISTURB ONE (1) OR MORE ACRES, HAS BEEN GRANTED COVERAGE UNDER THE TENNESSEE GENERAL STORM WATER PERMIT ADDRESSING CONSTRUCTION SITE RUNOFF ACTIVITIES BY THE TENNESSEE DIVISION OF WATER POLLUTION CONTROL." (TN# 241498)

Michael Towles
TN REGISTERED ENGINEER
04/17/2017
DATE

I, MICHAEL GREGORY TOWLES, A REGISTERED EROSION CONTROL SPECIALIST HAVE REVIEWED THE PLAN FOR SUFFICIENT ONSITE TEMPORARY EROSION AND SEDIMENT CONTROL PROVISIONS.

Michael Towles
EROSION CONTROL SPECIALIST
04/17/2017
DATE

NOTE:
CONTRACTOR TO PROVIDE AN AREA FOR CONCRETE WASH DOWN AND EQUIPMENT FUELING IN ACCORDANCE WITH METRO CP-10 AND CP-13, RESPECTIVELY. CONTRACTOR TO COORDINATE EXACT LOCATION WITH NPDES DEPARTMENT DURING PRE-CONSTRUCTION MEETING. CONTROL OF OTHER SITE WASTES SUCH AS DISCARDED BUILDING MATERIALS, CHEMICALS, LITTER, AND SANITARY WASTES THAT MAY CAUSE ADVERSE IMPACTS TO WATER QUALITY IS ALSO REQUIRED BY THE GRADING PERMITTEE.

SITE BM #1:
TAG BOLT #8229V7 ON FIRE HYDRANT LOCATED IN SOUTH ROW OF CROSSINGS BLVD ±750' WEST OF THE INTERSECTION OF CROSSINGS BLVD AND OLD FRANKLIN RD ELEV: 601.22

SITE BM #2:
BOLT BELOW ARROW ON FIRE HYDRANT LOCATED IN SOUTH ROW OF CROSSINGS BLVD ±255' WEST OF THE INTERSECTION OF CROSSINGS BLVD AND OLD FRANKLIN RD ELEV: 612.01

PROJECT BM:
NAVD 88 (GPS DERIVED)

SEDIMENT TRAP NOTES

- THE MAXIMUM EXCAVATION DEPTH OF THE SEDIMENT TRAP MUST BE AT LEAST 1 FOOT ABOVE THE POST CONSTRUCTION FINISHED GRADE.
- IF SEDIMENT TRAPS ARE INSTALLED IN THE SAME LOCATION AS BIO-RETENTION PONDS, THEN THE BIO-RETENTION POND MUST BE INSTALLED WITH AN UNDERDRAIN.
- WHEN CONVERTING THE SEDIMENT TRAP TO BIO-RETENTION:
 - DE-WATER THE SEDIMENT TRAP BY PUMPING THE REMAINING WATER THOUGH FILTERING DEVICE.
 - REMOVE SEDIMENT AND DISPOSE IN AN APPROVED LOCATION.
 - EXCAVATE TO THE PROPER DEPTH PER GRADING PLANS AND BIO-RETENTION DETAILS.
 - REPLACE TEMPORARY OUTLET STRUCTURE WITH PERMANENT OUTLET STRUCTURE.
 - INSTALL UNDERDRAIN AND BIO-RETENTION LAYERS PER PLANS AND DETAILS.
 - INSTALL FINAL STABILIZATION AND VEGETATION PER LANDSCAPE PLANS.
- INSPECT SEDIMENT TRAPS WEEKLY, BEFORE AND AFTER RAINFALL EVENTS. DURING EXTENDED RAINFALL EVENTS, INSPECT SEDIMENT TRAPS DAILY DURING CONSTRUCTION.
- EXAMINE TRAP BANKS FOR SEEPAGE AND STRUCTURAL SOUNDNESS.
- CHECK OUTLET STRUCTURE AND SPILLWAY FOR ANY DAMAGE OR OBSTRUCTIONS. REPAIR DAMAGE AND REMOVE OBSTRUCTIONS AS NEEDED.
- CHECK OUTLET AREA FOR EROSION AND STABILIZE, IF REQUIRED.
- REMOVE ACCUMULATED SEDIMENT WHEN THE VOLUME HAS REACHED ONE-THIRD THE ORIGINAL TRAP VOLUME. PROPERLY DISPOSE OF SEDIMENT AND DEBRIS REMOVED FROM THE TRAP.

EROSION CONTROL KEYNOTES		
CODE	DESCRIPTION	DET #/SHT #
EC1	TEMPORARY CONSTRUCTION ENTRANCE	
EC2	SILT FENCE OR WEIGHTED SEDIMENT TUBES	
EC3	INLET PROTECTION	
EC4	TREE PROTECTION	
EC5	DIVERSION DITCH	
EC6	ROCK CHECK DAM	
EC7	RIPRAP AT HEADWALL	
EC8a	SEDIMENT TRAP OUTLET STRUCTURE	
EC8b	TEMPORARY SEDIMENT TRAP	
EC9	TEMPORARY SEEDING OR MULCHING	
EC10	POROUS BAFFLE	
EC11	BIODEGRADABLE EROSION CONTROL BLANKETS WITH HYDRO SEEDING	
EC12	PERMANENT EROSION CONTROL BLANKETS WITH HYDRO SEEDING	

EROSION CONTROL NOTES:

- EROSION PREVENTION AND SEDIMENT CONTROL MEASURES MUST BE IN PLACE AND FUNCTIONAL BEFORE EARTH MOVING OPERATION BEGINS AND MUST BE CONSTRUCTED AND MAINTAINED THROUGHOUT THE CONSTRUCTION PERIOD. TEMPORARY MEASURES MAY BE REMOVED AT THE BEGINNING OF THE WORKDAY BUT MUST BE REPLACED AT THE END OF THE WORKDAY.
- THE FOLLOWING RECORDS SHALL BE MAINTAINED ON OR NEAR SITE: THE DATES WHEN MAJOR GRADING ACTIVITIES OCCUR; THE DATES WHEN CONSTRUCTION ACTIVITIES TEMPORARILY OR PERMANENTLY CEASE ON A PORTION OF THE SITE; THE DATES WHEN STABILIZATION MEASURES ARE INITIATED; INSPECTION RECORDS AND RAINFALL RECORDS.
- THE CONTRACTOR SHALL MAINTAIN A RAIN GAUGE AND DAILY RAINFALL RECORDS AT THE SITE OR USE A REFERENCE SITE FOR A RECORD OF DAILY AMOUNT OF PRECIPITATION.
- PRE-CONSTRUCTION VEGETATIVE GROUND COVER SHALL NOT BE DESTROYED, REMOVED OR DISTURBED MORE THAN 10 DAYS PRIOR TO GRADING OR EARTH MOVING UNLESS THE AREA IS SEEDED AND/OR MULCHED OR OTHER TEMPORARY COVER IS INSTALLED.
- CONSTRUCTION MUST BE SEQUENCED TO MINIMIZE THE EXPOSURE TIME OF GRADED OR DENUDED AREAS.
- STABILIZATION MEASURES SHALL BE INITIATED AS SOON AS POSSIBLE IN PORTIONS OF THE SITE WHERE CONSTRUCTION ACTIVITIES HAVE TEMPORARILY OR PERMANENTLY CEASED. TEMPORARY OR PERMANENT SOIL STABILIZATION AT THE CONSTRUCTION SITE (OR A PHASE OF THE PROJECT) MUST BE COMPLETED NO LATER THAN 14 DAYS AFTER THE CONSTRUCTION ACTIVITY IN THAT PORTION OF THE SITE HAS TEMPORARILY OR PERMANENTLY CEASED. IN THE FOLLOWING SITUATIONS, TEMPORARY STABILIZATION MEASURES ARE NOT REQUIRED:
 - WHERE THE INITIATION OF STABILIZATION MEASURES IS PRECLUDED BY SNOW COVER OR FROZEN GROUND CONDITIONS OR ADVERSE SOGGY GROUND CONDITIONS, STABILIZATION MEASURES SHALL BE INITIATED AS SOON AS PRACTICABLE; OR
 - WHERE CONSTRUCTION ACTIVITY ON A PORTION OF THE SITE IS TEMPORARILY CEASED, AND EARTH DISTURBING ACTIVITIES WILL BE RESUMED WITHIN 14 DAYS.
- STEEP SLOPES SHALL BE TEMPORARILY STABILIZED NOT LATER THAN 7 DAYS AFTER CONSTRUCTION ACTIVITY ON THE SLOPE HAS TEMPORARILY OR PERMANENTLY CEASED.
- PERMANENT STABILIZATION WITH PERENNIAL VEGETATION (USING NATIVE HERBACEOUS AND WOODY PLANTS WHERE PRACTICABLE) OR OTHER PERMANENTLY STABLE, NON-ERODING SURFACE SHALL REPLACE ANY TEMPORARY MEASURES AS SOON AS PRACTICABLE. UNPACKED GRAVEL CONTAINING FINES (SILT AND CLAY SIZED PARTICLES) OR CRUSHER RUNS WILL NOT BE CONSIDERED A NON-ERODING SURFACE.
- SEDIMENT SHOULD BE REMOVED FROM SEDIMENT TRAPS, SILT FENCES, SEDIMENTATION PONDS AND OTHER SEDIMENT CONTROLS AS NECESSARY AND MUST BE REMOVED WHEN DESIGN CAPACITY HAS BEEN REDUCED BY 50% OR AS DIRECTED BY OWNERS REPRESENTATIVE.
- THE CONTRACTOR SHALL REMOVE SEDIMENT FROM ALL DRAINAGE STRUCTURES BEFORE ACCEPTANCE BY LOCAL GOVERNING AGENCY OR AS DIRECTED BY THE OWNER'S REPRESENTATIVE.
- THE CONTRACTOR SHALL REMOVE THE TEMPORARY EROSION AND WATER POLLUTION CONTROL DEVICES ONLY AFTER A SOLID STAND OF GRASS HAS BEEN ESTABLISHED ON GRADED AREAS AND WHEN IN THE OPINION OF THE OWNER'S REPRESENTATIVE, THERE ARE NO LONGER NEEDED. THIS INCLUDES THE REMOVAL OF SILT FENCE, SEDIMENT TUBES, INLET PROTECTION, CHECK DAMS, FILTER RINGS, ETC.
- REFER TO THE LANDSCAPE PLANS FOR ADDITIONAL INFORMATION FOR FINAL STABILIZATION MEASURES INCLUDING FINAL VEGETATION, PLANTINGS, MULCHING, STONE, ETC.

SITE DESCRIPTION AND NOTES:


THE SITE IS LOCATED ON METRO TAX MAP 174, PARCEL 176 IN NASHVILLE, DAVIDSON COUNTY, TENNESSEE. CONSTRUCTION ACTIVITY ON THIS SITE WILL CONSIST OF DISTURBING APPROXIMATELY 13.26± ACRES TO CONSTRUCT A CORPORATE OFFICE FACILITY.

- APPROXIMATE CONSTRUCTION TIME TABLE:
 - BEGIN CONSTRUCTION [AUGUST 2017]
 - COMPLETE CONSTRUCTION [DECEMBER 2018]
- CONSTRUCTION SEQUENCE:
 - ATTEND METRO WATER SERVICES - WATER QUALITY DIVISION PRE-CONSTRUCTION MEETING.
 - INSTALL CONSTRUCTION ENTRANCE AND SILT FENCE
 - CONTACT METRO WATER SERVICES - WATER QUALITY DIVISION - EROSION CONTROL INSPECTOR FOR INSPECTION OF EROSION CONTROL DEVICES TO OBTAIN GRADING PERMIT.
 - ALL PERIMETER EPSC MEASURES SHALL BE IN PLACE BEFORE GRADING OPERATIONS BEGIN.
 - CLEAR AND GRUB THE REMAINING SITE.
 - CONSTRUCT REMAINING SITE ACCORDING TO APPROVED PLANS, INCLUDING ALL ADDITIONAL EROSION CONTROL DEVICES.
 - UPON PERMANENT SITE STABILIZATION SEED AND STRAW.
 - REMOVE ALL OTHER EROSION TEMPORARY CONTROL DEVICES PRIOR TO AS-BUILT APPROVALS.
- TOTAL PROJECT AREA = 595,874 SF (13.68± AC.)
DISTURBED AREA = 577,686 S.F. (13.26± AC.)

SWGR #


IN ACCORDANCE WITH THE METRO STORMWATER MANAGEMENT MANUAL, VOLUME 1, SECTION 3.9, AS-BUILT CERTIFICATIONS, MWS STORMWATER DIVISION MUST APPROVE THE FOLLOWING AS-BUILTS PRIOR TO ISSUANCE OF THE USE AND OCCUPANCY PERMIT:

- UNDERGROUND DETENTION AND WATER QUALITY INFRASTRUCTURE
- ABOVE GROUND DETENTION AND WATER QUALITY INFRASTRUCTURE
- PUBLIC STORM SEWER INFRASTRUCTURE
- CUT AND FILL IN THE FLOODPLAIN
- SINK HOLE ALTERATIONS



LEGEND

- INLET PROTECTION
- L O D LIMIT OF DISTURBANCE
- T P TREE PROTECTION FENCE
- S F SILT FENCE
- POROUS BAFFLE
- ROCK CHECK DAM
- TEMPORARY SEEDING OR MULCHING



KP NASHVILLE, LLC
8025 FORSYTH BLVD.
ST. LOUIS, MISSOURI
314-261-7352

FINAL P.U.D.
LKQ OFFICE AT
THE CROSSINGS
5846 CROSSINGS BLVD
NASHVILLE, TENNESSEE 37013
Case No. 84-87P-004

NO.	DATE	DESCRIPTION	BY	CHK	APV

PROJECT NUMBER
514717001
DRAWING NUMBER
C2.1
DRAWING NAME
INTERIM SEDIMENT
& EROSION
CONTROL PLAN

1. INSPECTIONS DESCRIBED IN PARAGRAPHS 2, 3 AND 4 BELOW, SHALL BE PERFORMED AT LEAST TWICE EVERY CALENDAR WEEK. INSPECTIONS SHALL BE PERFORMED AT LEAST 72 HOURS APART. WHERE SITES OR PORTION(S) OF CONSTRUCTION SITES HAVE BEEN TEMPORARILY STABILIZED, OR RUNOFF IS UNLIKELY DUE TO WINTER CONDITIONS (E.G., SITE COVERED WITH SNOW OR ICE) OR DUE TO EXTREME DROUGHT, SUCH INSPECTION ONLY HAS TO BE CONDUCTED ONCE PER MONTH UNTIL THAWING OR PRECIPITATION RESULTS IN RUNOFF OR CONSTRUCTION ACTIVITY RESUMES. INSPECTION REQUIREMENTS DO NOT APPLY TO DEFINABLE AREAS THAT HAVE BEEN PERMANENTLY STABILIZED. WRITTEN NOTIFICATION MUST BE SUBMITTED TO THE INSPECTION FREQUENCIES AND JUSTIFICATION FOR SUCH REQUEST MUST BE SUBMITTED TO THE LOCAL ENVIRONMENTAL FIELD OFFICE, OR THE DIVISION'S NASHVILLE CENTRAL OFFICE FOR PROJECTS OF THE TENNESSEE DEPARTMENT OF TRANSPORTATION (TDOT) AND THE TENNESSEE VALLEY AUTHORITY (TVA). SHOULD TDEC DISCOVER THAT MONTHLY INSPECTIONS OF THE SITE ARE NOT APPROPRIATE DUE TO INSUFFICIENT STABILIZATION MEASURES OR OTHERWISE, TWICE WEEKLY INSPECTIONS SHALL RESUME. TDEC MAY INSPECT THE SITE TO CONFIRM OR DENY THE NOTIFICATION TO CONDUCT MONTHLY INSPECTIONS.

2. QUALIFIED PERSONNEL (PROVIDED BY THE PERMITTEE OR COOPERATIVELY BY MULTIPLE PERMITTEES) SHALL INSPECT DISTURBED AREAS OF THE CONSTRUCTION SITE THAT HAVE NOT BEEN FINALLY STABILIZED, AREAS USED FOR STORAGE OF MATERIALS THAT ARE EXPOSED TO PRECIPITATION, STRUCTURAL CONTROL MEASURES, LOCATIONS WHERE VEHICLES ENTER OR EXIT THE SITE, AND EACH OUTFALL.

3. DISTURBED AREAS AND AREAS USED FOR STORAGE OF MATERIALS THAT ARE EXPOSED TO PRECIPITATION SHALL BE INSPECTED FOR EVIDENCE OF, OR THE POTENTIAL FOR, POLLUTANTS ENTERING THE SITE'S DRAINAGE SYSTEM. EROSION PREVENTION AND SEDIMENT CONTROL MEASURES SHALL BE OBSERVED TO ENSURE THAT THEY ARE OPERATING CORRECTLY.

4. **OUTFALL POINTS (WHERE DISCHARGES LEAVE THE SITE AND/OR ENTER WATERS OF THE STATE) SHALL BE INSPECTED TO DETERMINE WHETHER EROSION PREVENTION AND SEDIMENT CONTROL MEASURES ARE EFFECTIVE IN PREVENTING SIGNIFICANT IMPACTS TO RECEIVING WATERS. WHERE DISCHARGE LOCATIONS ARE INACCESSIBLE, NEARBY DOWNSTREAM LOCATIONS SHALL BE INSPECTED. LOCATIONS WHERE VEHICLES ENTER OR EXIT THE SITE SHALL BE INSPECTED FOR EVIDENCE OF OFFSITE SEDIMENT TRACKING.**

5. BASED ON THE RESULTS OF THE INSPECTION, ANY INADEQUATE CONTROL MEASURES OR CONTROL MEASURES IN DISREPAIR SHALL BE REPLACED OR MODIFIED, OR REPAIRED AS NECESSARY, BEFORE THE NEXT RAIN EVENT, BUT IN NO CASE MORE THAN 7 DAYS AFTER THE NEED IS IDENTIFIED.

6. BASED ON THE RESULTS OF THE INSPECTION, THE SITE DESCRIPTION AND POLLUTION PREVENTION MEASURES IDENTIFIED IN THIS SWPPP SHALL BE REVISED AS APPROPRIATE, BUT IN NO CASE LATER THAN 7 DAYS FOLLOWING THE INSPECTION. SUCH MODIFICATIONS SHALL PROVIDE FOR TIMELY IMPLEMENTATION OF ANY CHANGES TO THE SWPPP, BUT IN NO CASE LATER THAN 14 DAYS FOLLOWING THE INSPECTION.

7. ALL INSPECTIONS SHALL BE DOCUMENTED ON THE CONSTRUCTION STORMWATER INSPECTION CERTIFICATION FORM PROVIDED IN APPENDIX D OF THE SWPPP REPORT FOR ALL CONSTRUCTION SITES. INSPECTION DOCUMENTATION WILL BE MAINTAINED ON SITE AND MADE AVAILABLE TO TDEC UPON REQUEST. INSPECTION REPORTS MUST BE SUBMITTED TO TDEC WITHIN 10 DAYS OF THE REQUEST. IF TDEC REQUESTS THE CONSTRUCTION STORMWATER INSPECTION CERTIFICATION FORM TO BE SUBMITTED, THE INSPECTION FORM MUST CONTAIN THE PRINTED NAME AND SIGNATURE OF THE TRAINED CERTIFIED INSPECTOR AND THE PERSON WHO MEETS THE SIGNATORY REQUIREMENTS OF SECTION 7.7.2 OF THE NPDES GENERAL PERMIT.

8. TRAINED CERTIFIED INSPECTORS SHALL COMPLETE INSPECTION DOCUMENTATION TO THE BEST OF THEIR ABILITY. FALSIFYING INSPECTION RECORDS OR OTHER DOCUMENTATION OR FAILURE TO COMPLETE INSPECTION DOCUMENTATION SHALL RESULT IN A VIOLATION OF THIS PERMIT AND ANY OTHER APPLICABLE ACTS OR RULES.

9. SUBSEQUENT OPERATOR(S) (PRIMARY PERMITTEES) WHO HAVE OBTAINED COVERAGE UNDER THE NPDES GENERAL PERMIT SHOULD CONDUCT TWICE WEEKLY INSPECTIONS, UNLESS THEIR PORTION(S) OF THE SITE HAS BEEN TEMPORARILY STABILIZED, OR RUNOFF IS UNLIKELY DUE TO WINTER CONDITIONS OR DUE TO EXTREME DROUGHT AS STATED IN PARAGRAPH A) ABOVE. THE PRIMARY PERMITTEE (SUCH AS A DEVELOPER) IS NO LONGER REQUIRED TO CONDUCT INSPECTIONS OF PORTIONS OF THE SITE THAT ARE COVERED BY A SUBSEQUENT PRIMARY PERMITTEE (SUCH AS A HOME BUILDER).

1. THE SITE ASSESSMENT SHALL BE PERFORMED BY INDIVIDUALS WITH THE FOLLOWING QUALIFICATIONS:
 - A LICENSED PROFESSIONAL ENGINEER OR LANDSCAPE ARCHITECT
 - A CERTIFIED PROFESSIONAL IN EROSION AND SEDIMENT CONTROL (CPESC) OR
 - A PERSON THAT SUCCESSFULLY COMPLETED THE "LEVEL II DESIGN PRINCIPLES FOR EROSION PREVENTION AND SEDIMENT CONTROL FOR CONSTRUCTION SITES" COURSE.

2. QUALITY ASSURANCE OF EROSION PREVENTION AND SEDIMENT CONTROLS SHALL BE DONE BY PERFORMING SITE ASSESSMENT AT A CONSTRUCTION SITE. THE SITE ASSESSMENT SHALL BE CONDUCTED AT EACH OUTFALL INVOLVING DRAINAGE TOTALING 10 OR MORE ACRES OR 5 OR MORE ACRES IF DRAINING TO AN IMPAIRED OR EXCEPTIONAL QUALITY WATERS, WITHIN A MONTH OF CONSTRUCTION COMMENCING AT EACH PORTION OF THE SITE THAT DRAINS THE QUALIFYING ACREAGE OF SUCH PORTION OF THE SITE.

3. AS A MINIMUM, SITE ASSESSMENT SHOULD BE PERFORMED TO VERIFY THE INSTALLATION, FUNCTIONALITY AND PERFORMANCE OF THE EPSM MEASURES DESCRIBED IN THE SWPPP REPORT. THE SITE ASSESSMENT SHOULD BE PERFORMED WITH THE INSPECTOR, AND SHOULD INCLUDE A REVIEW AND UPDATE (IF APPLICABLE) OF THE SWPPP REPORT. MODIFICATIONS OF PLANS AND SPECIFICATIONS FOR ANY BUILDING OR STRUCTURE, INCLUDING THE DESIGN OF SEDIMENT BASINS OR OTHER SEDIMENT CONTROLS INVOLVING STRUCTURAL, HYDRAULIC, HYDROLOGIC, OR HYDROLOGICAL ENGINEERING CALCULATIONS SHALL BE PREPARED BY A LICENSED PROFESSIONAL ENGINEER OR LANDSCAPE ARCHITECT AND STAMPED AND CERTIFIED IN ACCORDANCE WITH THE TENNESSEE CODE ANNOTATED, TITLE 62, CHAPTER 2 AND THE RULES OF THE TENNESSEE BOARD OF ARCHITECTURAL AND ENGINEERING EXAMINERS.

4. THE SITE ASSESSMENT FINDINGS SHALL BE DOCUMENTED AND THE DOCUMENTATION KEPT WITH THE SWPPP REPORT AT THE SITE. AT A MINIMUM, THE DOCUMENTATION SHALL INCLUDE INFORMATION INCLUDED IN THE INSPECTION FORM PROVIDED IN APPENDIX D OF THE SWPPP REPORT. THE DOCUMENTATION MUST CONTAIN THE PRINTED NAME AND SIGNATURE OF THE INDIVIDUAL PERFORMING THE SITE ASSESSMENT AND THE FOLLOWING CERTIFICATION:

"I CERTIFY UNDER PENALTY OF LAW THAT THIS REPORT AND ALL ATTACHMENTS ARE, TO THE BEST OF MY KNOWLEDGE AND BELIEF, TRUE, ACCURATE, AND COMPLETE. I AM AWARE THAT THERE ARE SIGNIFICANT PENALTIES FOR SUBMITTING FALSE INFORMATION, INCLUDING THE POSSIBILITY OF FINE AND IMPRISONMENT FOR KNOWING VIOLATIONS."

5. THE SITE ASSESSMENT CAN TAKE THE PLACE OF ONE OF THE TWICE WEEKLY INSPECTIONS REQUIREMENT.


6. TDEC MAY REQUIRE ADDITIONAL SITE ASSESSMENT(S) TO BE PERFORMED IF SITE INSPECTION BY TDEC'S PERSONNEL REVEALS SITE CONDITIONS THAT HAVE POTENTIAL OF CAUSING POLLUTION TO THE WATERS OF THE STATE.

CONTRACTOR SHALL INSTALL A 4'X4' WEATHER PROOF SIGN (6' HEIGHT) AT THE MAIN CONSTRUCTION ENTRANCE. THE SIGN SHALL HAVE THE FOLLOWING INFORMATION:

1. A COPY OF THE NOTICE OF COVERAGE WITH THE NPDES PERMIT NUMBER (FURNISHED BY ENGINEER).
2. THE NAME AND TELEPHONE NUMBER OF A LOCAL CONTACT PERSON (FURNISHED BY CONSTRUCTION MANAGER).
3. DESCRIPTION OF PROJECT (FURNISHED BY CONSTRUCTION MANAGER).



NO SCALE




*TENSAR NORTH AMERICAN GREEN TYPE SC250 PERMANENT EROSION CONTROL BLANKETS TO BE INSTALLED ON SLOPES STEEPER THAN 3:1.	*TENSAR NORTH AMERICAN GREEN TYPE SC150 TEMPORARY BIODEGRADABLE EROSION CONTROL BLANKETS OR APPROVED EQUIVALENT TO BE INSTALLED ON SLOPES 3:1 OR LESS.	NOTE: DETAIL PROVIDED BY TENSAR. NORTH AMERICAN GREEN. REFER TO MANUFACTURER FOR ADDITIONAL DETAILS.
--	--	---

NO SCALE




NO SCALE



NO SCALE




NO SCALE




Volume 4: Stormwater Best Management Practices – Temp. Construction Management Practices	TCP-14-6	August 2009
--	----------	-------------

[illegible]



PROJECT NUMBER	514717001
DRAWING NUMBER	C2.4
DRAWING NAME	EPSC DETAILS

DEMOLITION KEYNOTES		
CODE	DESCRIPTION	DET #/SHT #
D1	REMOVE EXISTING ASPHALT PAVEMENT	
D2a	REMOVE EXISTING CONCRETE PAVEMENT	
D2b	REMOVE EXISTING CONCRETE SIDEWALK	
D3	REMOVE EXISTING CONCRETE CURB	
D4	EVENLY SAWCUT	
D5	REMOVE EXISTING BUILDING/STRUCTURE	
D6	REMOVE EXISTING DRAINAGE STRUCTURE	
D7	REMOVE EXISTING STORM LINE	
D8	REMOVE EXISTING WATERLINE & APPURTENANCES	
D9	REMOVE EXISTING SANITARY SEWER LINE	
D10	REMOVE EXISTING UTILITY LINE & APPURTENANCES	
D11	EXISTING UTILITY LINE TO BE ABANDONED IN PLACE	
D12	EXISTING HYDRANT TO BE RELOCATED	
D13	REMOVE EXISTING TREE	



G:\Projects\2017\514717001\dwg\Construction\514717001-C-C3.0 DEM.dwg-C3.0 DEMOLITION Apr 14, 2017 cpaul



Littlejohn
A Division of S&ME

1935 21st Avenue South, NASHVILLE, TENNESSEE 37212
T 615.385.4144 F 615.385.4020 www.littlejohn.com

KP NASHVILLE, LLC
8025 FORSYTH BLVD.
ST. LOUIS, MISSOURI
314-261-7352

FINAL P.U.D.
LKQ OFFICE AT
THE CROSSINGS
5846 CROSSINGS BLVD
NASHVILLE, TENNESSEE 37013

[illegible]

PROJECT NUMBER	514717001
DRAWING NUMBER	C3.0
DRAWING NAME	SITE DEMOLITION

SITE LAYOUT KEYNOTES		
CODE	DESCRIPTION	DET #/SHT #
S1a	ASPHALT PAVEMENT - LIGHT DUTY	
S1b	ASPHALT PAVEMENT - HEAVY DUTY	
S1c	ASPHALT PAVEMENT - OVERLAY	
S1d	ASPHALT PAVEMENT (METRO STANDARD DETAIL)	
S2	CONCRETE PAVEMENT	
S3a	CONCRETE CURB & GUTTER	
S3b	CONCRETE POST CURB	
S3c	CONCRETE EXTRUDED CURB	
S4a	CONCRETE SIDEWALK	
S4b	CONCRETE SIDEWALK WITH TURN DOWN CURB	
S4c	CONCRETE SIDEWALK AT CURB & GUTTER	
S5	SIDEWALK JOINTS	
S6	ACCESSIBLE SYMBOL	
S7	ACCESSIBLE PARKING SPACE	
S8a	ACCESSIBLE RAMP	
S8b	ACCESSIBLE WINGED RAMP	
S9	TACTILE WARNING SURFACE	
S10	CONCRETE WHEELSTOP	
S11a	CONCRETE STAIRS WITH HANDRAIL	
S11b	CONCRETE STAIRS WITH HANDRAIL/GUARDRAIL	
S12	ELEVATED WALK	
S13a	RAMP WITH HANDRAIL	
S13b	RAMP WITH HANDRAIL/GUARDRAIL	
S14	BOLLARD	
S15	UTILITY PAD	
S16	CONCRETE DUMPSTER PAD	
S17	DRIVEWAY RAMP	
S18	DIRECTIONAL ARROWS	
S19	PEDESTRIAN CROSSWALK	
S20a	CHAIN LINK FENCE (SPECIFY HEIGHT)	
S20b	WOODEN SCREEN FENCE (SPECIFY HEIGHT)	
S21a	GUARDRAIL	
S21b	GUARDRAIL WITH HANDRAIL	
S22a	CONCRETE RETAINING WALL	
S22b	SEGMENTAL RETAINING WALL	
S23	PAINTED STOP BAR (SPECIFY WIDTH)	

LINE TABLE		
LINE #	LENGTH	BEARING
L1	176.76	S23° 55' 38"W
L2	213.06	S4° 48' 20"W
L3	60.45	S4° 48' 20"W
L4	70.53	S4° 48' 20"W
L5	120.90	S4° 48' 20"W
L6	75.29	S4° 48' 20"W
L7	60.45	S4° 48' 20"W
L8	25.06	S4° 48' 20"W
L9	214.92	N78° 11' 39"W
L10	20.00	N11° 48' 21"E
L11	297.67	N78° 11' 39"W

LINE TABLE		
LINE #	LENGTH	BEARING
L12	305.04	N78° 11' 39"W
L13	314.22	S78° 11' 39"E
L14	60.00	N11° 48' 21"E
L15	74.73	N11° 48' 21"E
L16	280.94	S78° 11' 39"E
L17	60.00	N11° 48' 21"E
L18	185.99	N78° 11' 39"W
L19	60.21	S7° 00' 21"W
L20	180.96	S78° 11' 39"E
L21	328.95	S78° 11' 39"E
L22	337.55	S78° 11' 39"E








LINE TABLE		
LINE #	LENGTH	BEARING
L23	200.40	S78° 11' 39"E
L24	144.51	S78° 11' 39"E
L25	125.39	S11° 48' 21"W
L26	81.91	N73° 34' 14"W
L27	23.00	N11° 48' 21"E
L28	388.00	S78° 11' 39"E
L29	60.00	N11° 48' 21"E
L30	425.00	S78° 11' 39"E
L31	60.00	N11° 48' 21"E
L32	70.00	N11° 48' 21"E
L33	60.00	N11° 48' 21"E


CURVE TABLE					
CURVE #	LENGTH	RADIUS	DELTA	CHORD DIRECTION	CHORD LENGTH
C1	45.37	200.00	13.00	S17° 25' 45"W	45.27
C2	57.94	40.00	83.00	S36° 41' 39"E	53.01
C3	62.83	40.00	90.00	N56° 48' 21"E	56.57
C4	58.12	37.00	90.00	S56° 48' 21"W	52.33
C5	21.38	200.00	6.13	S7° 52' 06"W	21.37




Know what's below.
Call before you dig.

PROPOSED FEATURES LEGEND

- | | |
|--------------------|---|
| BUILDING |  |
| CURB AND GUTTER |  |
| POST CURB |  |
| CONCRETE SIDEWALK |  |
| CONCRETE PAVEMENT |  |
| HEAVY-DUTY ASPHALT |  |
| LIGHT-DUTY ASPHALT |  |



VICINITY MAP
NO SCALE




NOTES:

1. ALL SIGNS SHALL BE 3M, HIGH INTENSITY, REFLECTIVE MATERIAL.
2. ALL PAVEMENT MARKINGS SHALL BE THERMOPLASTIC.
3. ALL STRIPING AND SIGNAGE SHALL BE IN ACCORDANCE WITH THE "MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES" (MUTCD) FOR STREETS AND HIGHWAYS.
4. SIGNS TO BE PLACED 2' FROM BACK OF CURB SIGN HT. TO BE 7' FROM BOTTOM OF SIGN TO ROAD SURFACE.
5. ALL STRIPING TO BE 4" WIDE UNLESS OTHERWISE INDICATED.
6. ALL STRIPING TO BE THERMOPLASTIC.
7. OBLITERATE EXISTING STRIPING & RESTRIPE TO PROPOSED CONFIGURATION.

PAVEMENT MARKING

- | | |
|------|---------------------------|
| SSWL | SINGLE SOLID WHITE LINE |
| SBWL | SINGLE BROKEN WHITE LINE |
| DSYL | DOUBLE SOLID YELLOW LINE |
| SBYL | SINGLE BROKEN YELLOW LINE |
| SSYL | SINGLE SOLID YELLOW LINE |



Littlejohn
A Division of S&ME

1935 21st Avenue South, Nashville, Tennessee 37212
T 615.385.4144 F 615.385.4020 www.leaninc.com

www.leadinc.com

KP NASHVILLE, LLC

8025 FORSYTH BLVD.

ST. LOUIS, MISSOURI

314-261-7352

FINAL P.U.D.

LKO OFFICE AT

THE CROSSINGS

5846 CROSSINGS BLVD

NASHVILLE, TENNESSEE 37013

[illegible]

PROJECT NUMBER
514717001

DRAWING NUMBER

C4.0

DRAWING NAME

SITE LAYOUT


GRADING & DRAINAGE KEYNOTES		
CODE	DESCRIPTION	DET #/SHT #
G1a	CURB INLET	4/C7.2
G1b	DOUBLE CURB INLET	5/C7.2
G1c	TRIPLE CURB INLET	6/C7.2
G1d	DOUBLE CURB INLET (PUBLIC)	6/C7.1
G2a	CATCH BASIN	8/C7.1
G3	JUNCTION MANHOLE	1/C7.3
G4	NYLOPLAST JUNCTION	9/C7.3
G6	CONCRETE HEADWALL - WINGED	2/C7.3
G7	BUILDING ROOF LEADER CONNECTION	
G9	BMP OUTLET STRUCTURE	6/C7.3
G15	RIPRAP AT HEADWALL	
G16a	LEVEL 2 BIORETENTION AREA	1, 2, 3/C7.2
G16b	FOREBAY BERM	4/C7.3
G16c	6" PERFORATED HDPE UNDERDRAIN	
G17	TRANSITION FROM FLUSH CONDITION TO 6" CURB OVER 5 FEET	
G18	GRASS SWALE	5/C7.3



Know what's below.
Call before you dig.

PROPOSED FEATURES LEGEND

- STORM PIPE & INLET
- SPOT ELEVATION + 91.8
- PROPOSED CONTOUR 90
- DRAINAGE STRUCTURE C3





Littlejohn

A Division of S&ME

KP NASHVILLE, LLC
8025 FORSYTH BLVD.
ST. LOUIS, MISSOURI
314-261-7352

FINAL P.U.D.
LQO OFFICE AT
THE CROSSINGS
5846 CROSSINGS BLVD
NASHVILLE, TENNESSEE 37013
Case No. 84-87P-004

NO.	DATE	DESCRIPTION	BY	CHK	APV

PROJECT NUMBER
514717001

DRAWING NUMBER
C5.0

DRAWING NAME
SITE GRADING &
DRAINAGE

PIPE TABLE							
FROM CODE	FROM INV	TO CODE	TO INV.	GRADE (%)	SIZE (INCHES)	LENGTH (L.F.)	TYPE
A2	599.80	A1	599.00	1.37%	36"	59	RCP
A3	600.50	A2	600.00	1.35%	30"	37	RCP
A4	601.50	A3	600.70	0.72%	30"	111	RCP
A5	605.00	A4	601.70	1.25%	24"	263	RCP
A6	609.00	A5	605.20	2.76%	18"	138	RCP
A7	610.00	A6	609.20	2.36%	18"	34	RCP
A8	618.00	A7	610.20	6.72%	18"	116	RCP
A9	629.00	A8	618.20	7.20%	18"	150	RCP
A10	640.00	A9	629.20	7.20%	18"	150	RCP
A11	650.00	A10	640.20	6.53%	18"	150	RCP
A12	658.00	A11	650.20	7.10%	18"	110	RCP
A13	662.00	A12	658.20	3.79%	18"	100	RCP
A14	662.80	A13	662.20	2.25%	18"	27	RCP
B1	604.80	A2	600.00	3.88%	24"	124	HDPE
B2	608.30	B1	605.00	2.61%	24"	127	HDPE
B3	613.68	B2	608.50	2.49%	18"	208	HDPE
B4	617.80	B3	613.88	2.49%	18"	158	HDPE
B5	624.80	B4	618.00	4.92%	18"	138	HDPE
B6	630.00	B5	625.00	2.75%	18"	182	HDPE
C1	602.00	A4	601.50	1.09%	24"	46	HDPE
D1	606.00	B1	605.00	2.64%	12"	38	HDPE
E2	609.10	E1	609.00	0.50%	24"	20	RCP
E3	614.41	E2	609.30	1.90%	18"	270	HDPE
E4	616.20	E3	614.61	1.90%	18"	84	HDPE
E5	618.00	E4	616.20	1.71%	15"	105	HDPE
E6	621.00	E5	618.20	1.75%	12"	160	HDPE
F1	613.20		613.00	1.74%	15"	12	RCP
G1	613.80		613.00	6.95%	18"	12	RCP
G2	616.08	G1	614.00	1.02%	18"	204	HDPE
G3	618.70	G2	616.28	1.00%	15"	242	HDPE



PIPE TABLE							
FROM CODE	FROM INV	TO CODE	TO INV.	GRADE (%)	SIZE (INCHES)	LENGTH (L.F.)	TYPE
G4	620.51	G3	618.90	1.00%	15"	161	HDPE
G5	621.40	G4	620.71	1.00%	15"	69	HDPE
G6	623.00	G5	621.60	1.00%	12"	140	HDPE
H1	608.80	B2	608.50	1.43%	18"	21	HDPE
H2	611.00	H1	609.00	3.78%	15"	53	HDPE
I2	616.40	I1	616.00	1.71%	18"	23	HDPE
I3	618.31	I2	616.60	1.31%	15"	131	HDPE
I4	620.39	I3	618.51	1.31%	15"	144	HDPE
I5	623.60	I4	620.59	2.08%	12"	144	HDPE
I6	626.00	I5	623.80	2.22%	12"	99	HDPE
I7	629.00	I6	626.20	7.66%	12"	37	HDPE
J1	626.00	I4	620.59	4.42%	12"	122	HDPE
K1	616.20	B3	613.88	11.01%	12"	21	HDPE
L1	620.00	B4	618.00	1.33%	18"	151	HDPE
M2	626.20	M1	626.00	1.01%	18"	20	HDPE
M3	627.00	M2	626.40	0.80%	18"	75	HDPE
M4	628.00	M3	627.20	0.55%	15"	146	HDPE
N2	609.20	N1	609.00	1.08%	15"	18	HDPE
O1	619.80	G1	614.00	4.41%	10"	132	HDPE
O2	622.60	O1	620.00	1.28%	10"	203	HDPE
O3	623.00	O2	622.80	1.92%	10"	10	HDPE
P1	623.00	G5	621.60	8.26%	8"	17	HDPE
Q1	623.00	G2	616.28	36.58%	10"	18	HDPE
R1	607.00	A5	605.20	5.19%	18"	35	HDPE

STRUCTURE TABLE		
CODE	DESCRIPTION	TOP GRATE
G2	36" CATCH BASIN	624.50
G3	48" SLAB TOP MANHOLE	631.00
G4	48" SLAB TOP MANHOLE	627.75
G5	48" SLAB TOP MANHOLE	627.75
G6	ROOF LEADER	N/A
H1	36"x72" DOUBLE CURB INLET	614.70
H2	36" CATCH BASIN	617.00
I1	6' HEADWALL	N/A
I2	36"x72" DOUBLE CURB INLET	620.50
I3	36"x72" DOUBLE CURB INLET	626.00
I4	36"x72" DOUBLE CURB INLET	628.17
I5	48" CONCENTRIC MANHOLE	628.50
I6	36"x72" DOUBLE CURB INLET	633.00
I7	36"x72" DOUBLE CURB INLET	637.25
J1	36"x72" DOUBLE CURB INLET	630.50
K1	36"x72" DOUBLE CURB INLET	622.40
L1	36" CATCH BASIN	627.00
M1	6' HEADWALL	N/A
M2	36"x36" SINGLE CURB INLET	630.00
M3	36"x72" DOUBLE CURB INLET	632.25
M4	36"x72" DOUBLE CURB INLET	632.75
N1	6' HEADWALL	N/A
N2	36"x72" DOUBLE CURB INLET	612.00
O1	NYLOPLAST JUNCTION	626.50
O2	NYLOPLAST JUNCTION	626.25
O3	ROOF LEADER	N/A
P1	ROOF LEADER	N/A
Q1	ROOF LEADER	N/A
R1	36" CATCH BASIN	614.00

STRUCTURE TABLE		
CODE	DESCRIPTION	TOP GRADE
A1	6" HEADWALL	N/A
A2	36"X72" DOUBLE CURB INLET	605.80
A3	36"X72" DOUBLE CURB INLET	605.70
A4	48" CONCENTRIC MANHOLE	608.00
A5	48" CONCENTRIC MANHOLE	611.00
A6	36" CATCH BASIN	613.50
A7	36"X72" DOUBLE CURB INLET	614.80
A8	36"X72" DOUBLE CURB INLET	623.80
A9	36"X72" DOUBLE CURB INLET	635.60
A10	36"X72" DOUBLE CURB INLET	646.80
A11	36"X72" DOUBLE CURB INLET	656.75
A12	36"X72" DOUBLE CURB INLET	663.80
A13	36"X72" DOUBLE CURB INLET	667.90
A14	36" CATCH BASIN	667.50
B1	36"X72" DOUBLE CURB INLET	610.00
B2	36"X72" DOUBLE CURB INLET	614.70
B3	36"X72" DOUBLE CURB INLET	622.25
B4	36"X72" DOUBLE CURB INLET	628.75
B5	48" CONCENTRIC MANHOLE	633.25
B6	48" CATCH BASIN	637.00
C1	36" CATCH BASIN	609.00
D1	36"X72" DOUBLE CURB INLET	610.10
E1	6" HEADWALL	N/A
E2	36"X72" DOUBLE CURB INLET	612.00
E3	48" SLAB TOP MANHOLE	621.80
E4	36"X108" TRIPLE CURB INLET	621.80
E5	36"X36" SINGLE CURB INLET	625.00
E6	36"X72" DOUBLE CURB INLET	626.50
F1	36"X72" DOUBLE CURB INLET	617.00
G1	36"X36" SINGLE CURB INLET	621.90



**Know what's below.
Call before you dig.**



VICINITY MAP
NO SCALE

GRADING & DRAINAGE KEYNOTES		
CODE	DESCRIPTION	DET #/SHT #
G1a	CURB INLET	4/C7.2
G1b	DOUBLE CURB INLET	5/C7.2
G1c	TRIPLE CURB INLET	6/C7.2
G1d	DOUBLE CURB INLET (PUBLIC)	6/C7.1
G2a	CATCH BASIN	8/C7.1
G3	JUNCTION MANHOLE	1/C7.3
G4	NYLOPLAST JUNCTION	9/C7.3
G6	CONCRETE HEADWALL - WINGED	2/C7.3
G7	BUILDING ROOF LEADER CONNECTION	.
G9	BMP OUTLET STRUCTURE	6/C7.3
G15	RIRAP AT HEADWALL	
G16a	LEVEL 2 BIORETENTION AREA	1, 2, 3/C7.2
G16b	FOREBAY BERM	4/C7.3
G16c	6" PERFORATED HDPE UNDERDRAIN	.
G17	TRANSITION FROM FLUSH CONDITION TO 6" CURB OVER 5 FEET	.
G18	GRASS SWALE	5/C7.3

IN ACCORDANCE WITH THE METRO STORMWATER MANAGEMENT MANUAL, VOLUME 1, SECTION 3.9, AS-BUILT CERTIFICATIONS, MWS STORMWATER DIVISION MUST APPROVE THE FOLLOWING AS-BUILTS PRIOR TO ISSUANCE OF THE USE AND OCCUPANCY PERMIT:

- A CERTIFICATION LETTER FROM TN REGISTERED P.E. STATING THAT THE SITE HAS BEEN INSPECTED AND THAT THE STORMWATER MANAGEMENT SYSTEM AND STORMWATER CONTROL MEASURES (BOTH STRUCTURAL AND NON-STRUCTURAL) ARE COMPLETE AND FUNCTIONAL IN ACCORDANCE WITH THE PLANS APPROVED BY MWS.
- AN AS-BUILT LID SPREADSHEET.
 - HYDROLOGIC AND HYDRAULIC CALCULATIONS FOR AS-BUILT CONDITIONS, AS REQUIRED.
 - AS-BUILT DRAWINGS SHOWING FINAL TOPOGRAPHIC FEATURES OF ALL THESE FACILITIES. THIS SHALL INCLUDE INVERT ELEVATIONS OF OUTLET CONTROL STRUCTURES.
 - ANY DEVIATIONS FROM THE APPROVED PLANS SHALL BE NOTED ON AS-BUILT DRAWINGS SUBMITTED.
 - COPY OF AS-BUILT PLAN CAD FILE ON A CD AND SHOULD BE REGISTERED TO THE TN STATE PLANE COORDINATE SYSTEM, NORTH AMERICAN DATUM 1983 (NAD83). DATA SHOULD BE PLACED IN SEPARATE LAYERS AND SHOULD BE LABELED / NAMED FOR EASY IDENTIFICATION.
 - CUT AND FILL BALANCE CERTIFICATION FOR FLOODPLAIN AND SINKHOLE ALTERATIONS.
 - WATER QUALITY BUFFERS SHALL BE SURVEYED AND INCLUDED WITH THE AS-BUILT SUBMITTAL.
 - ANY PUBLIC (TO BECOME THE RESPONSIBILITY OF METRO TO MAINTAIN) STORMWATER INFRASTRUCTURE SHALL BE VIDEO-INSPECTED TO VERIFY PROPER INSTALLATION WITH THE VIDEO RECORDING AND ANY ASSOCIATED INSPECTION REPORT SUBMITTED AS PART OF AS-BUILT RECORD.
 - ADDITIONAL TESTING MAY BE REQUIRED AS/IF WARRANTED BY VIDEO INSPECTION.


PROPOSED FEATURES LEGEND

STORM PIPE & INLET

SPOT ELEVATION

PROPOSED CONTOUR

DRAINAGE STRUCTURE



FINAL P.U.D.
LKQ OFFICE AT
THE CROSSINGS
5846 CROSSINGS BLVD
NASHVILLE, TENNESSEE 37013
Case No. 84-87P-004

KP NASHVILLE, LLC
8025 FORSYTH BLVD
ST. LOUIS, MISSOURI
314-261-7352



Littlejohn
A Division of S&ME

1935 21st Avenue South, NASHVILLE, TENNESSEE 37212
T 615.385.4144 F 615.385.4020 www.leaninc.com


[illegible]

PROJECT NUMBER
514717001

DRAWING NUMBER

DRAWING NAME
DETAILED GRADING
& DRAINAGE
TABLES


[illegible]



5

DOUBLE CURB INLET (PRIVATE)


NO SCALE



3

BIORETENTION AREA D


NOT TO SCALE



1

BIORETENTION AREA B & C


NOT TO SCALE



6

TRIPLE CURB INLET (PRIVATE)


NO SCALE



4

SINGLE CURB INLET (PRIVATE)

NO SCALE



2

BIORETENTION AREA A

NOT TO SCALE

